Central Registry (120-5-18-8) SG- building construction - meeting halls covering over FDR Drive - FTWS Inc

01 Dec 1950
15 Dec 1950

CLEAR
AT 8/04

S-0472
Box 28
File 6

(RAG-1)

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT HQ 1/75-MEETING HALLS

ESTIMATE FOR CHANGE NO. 19 - DATED DECEMBER 15, 1950

BREAKDOWN OF PRICES

I - SECTIONS 2, 3, 4 - CONCRETE AND CEMENT WORK
(Brennan & Sloan, Inc.)

	ADD	DEDUCT
1) Add 33 SF slab forms @ $0.568/sf	$ 18.74	---
2) Add 20 LF reglet @ $.25/lf	5.00	---
3) Add 0.13 TONS reinf. steel @ $247.40/ton	32.16	---
4) Add 5 CY 3000# Concrete @ $14.42/cy	72.10	---
5) Omit 4 CY Gritcrete @ $13.27/cy	---	$ 53.08
	$ 128.00	$ 53.08
	53.08	
	$ 74.92	
12% Labor Increase	4.16	
15% O & P	11.86	
FOAB & UI:	1.75	
TOTAL ADDITION	$ 92.69	

II - SECTIONS 5 & 6 - MASONRY & MORTARS
(J. Harry McNally Mason Corp.)

	ADD	DEDUCT
1) Add Jumbo Sand Lime Brick - 5000 Ea.		
Material.....	$ 193.80	---
Labor.....	$ 343.20	---
2) Add 6" hollow cinder block- 230 SF		
Material.....	$ 43.47	---
Labor.....	$ 71.30	---
3) Add 8" hollow cinder block- 150 SF		
Material.....	$ 35.25	---
Labor.....	$ 69.00	---
4) Add Premoulded Joint - 30 SF		
Material.....	$ 12.30	---
Labor.....	$ 8.40	---
	$ 776.72	---
15% O & P	116.51	
FOAB & UI:	22.14	
TOTAL ADDITION	$ 915.37	

III - SECTION 9 - CUT STONE
(A.T. Petrillo Co.)

	ADD	DEDUCT
1) Add new pier at Col. 20R' West Elevation		
Stone..... 307.67		
Breakage..... 30.77		
Anchor, Mortar..... 37.50		
Field Labor..... 401.85		
Shop Labor..... 416.92		
Insurance..... 70.87		
Welfare & Holidays..... 24.56		
1290.14	$1290.14	---
	$1290.14	---
15% O & P	193.52	
TOTAL ADDITION	$1483.66	

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT HQ 1/75-MEETING HALLS

ESTIMATE FOR CHANGE NO. 19-DATED DECEMBER 15, 1950

BREAKDOWN OF PRICES

		ADD	DEDUCT
IV -	SECTIONS 11 & 12 - MISC. & ORNA. IRON (General Bronze Corp.)		
1)	Omit 16" x 4" x 3/8" plate at post centers, interior railing W. Wall @ 68'-4" Mat.....215# @ $.15	---	$ 32.25
2)	Add 7" x 4" x 7/16" angle, continuous at interior railing W. Wall @ 68'-4" Mat.....1700# @ $.10	$ 170.00	---
3)	Omit 1 bay of windows from W. Elevation Mat.....$270.00 Shop..... 426.00 Erect..... 181.00 $877.00 FOAB & UI: ($12.00 Cr.)	---	$ 877.00
4)	Increase girth of all sill members and change steel springs in mullions to stainless steel. Mat.....$387.00 Shop..... 271.00 $658.00 FOAB & UI:($5.00)	$ 658.00	---
5)	Add interior steel trim W. Wall Mat.....$100.00 Draft..... 99.00 Shop..... 765.00 Erect..... 303.00 $1267.00 FOAB & UI: ($23.00	$1,267.00	---
6)	Add aluminum filler at Col. 15S Secretariat. Add vertical expansion joint at neck Increase width of Bronzalun Plates. C.E. Halback's Sub-Contract charge to General Bronze Corp. Mat.....$110.00 Shop..... 198.00 Field..... 198.00 Eng..... 44.00 $550.00	$ 550.00	---
		$2,645.00	$ 909.25
		909.25	
		$1,735.75	
	15% O & P	260.36	
	FOAB & UI	16.00	
	TOTAL ADDITION	$2,012.11	

		ADD	DEDUCT
V -	SECTION 13 - CONSTRUCTION INSULATION (William J. Scully, Inc.)		
1)	Furnish and install vertical flexible "Fibreglas" insulation wrapped in membrane at North and South ends of West Wall - Column Line R'.	$ 282.61	---
		$ 282.61	---
	15% O & P	42.39	
	TOTAL ADDITION	$ 325.00	

FULLER-TURNER-WALSH-SIATTERY, INC.
UNITED NATIONS CONTRACT HQ 1/75-MEETING HALLS

ESTIMATE FOR CHANGE NO. 19-DATED DECEMBER 15, 1950

BREAKDOWN OF PRICES

	ADD	DEDUCT
VI - SECTION 20 - FURRING AND LATHING (Jeremiah Burns, Inc.)		
1) Add 32 LF Plaster stop @ $.35/lf	$ 11.20	---
2) Increased labor cost	0.90	---
	$ 12.10	---
15% O & P	1.82	
TOTAL ADDITION	$ 13.92	

	ADD	DEDUCT
VII - SECTION 21 - PLASTERING (T. A. O'Rourke, Inc.)		
1) Add 34 SY 2-coat plaster @ $1.70/sy	$ 57.80	---
2) Add 25 LF base screed @ $.20/lf	5.00	---
	$ 62.80	---
15% O & P	9.42	
TOTAL ADDITION	$ 72.22	

	ADD	DEDUCT
VIII - SECTION 24 - GLASS & GLAZING (AbbottGlass Co., Inc.)		
1) Omit 246 SF 3/8" Pol. plate @ $.87/sf	---	$ 214.02
2) Omit 48 SF 1/4" Pol. wire @ $.86/sf	---	$ 41.28
		$ 255.30
N.Y.C. Sales Tax		5.11
TOTAL DEDUCTION		$ 260.41

	ADD	DEDUCT
IX - SECTION 26 - PAINT & FINISH (J. I. Hass Co., Inc.)		
1) Add 306 SF Paint on Plaster @ $.10/sf	$ 30.60	---
2) Add 25 LF taped base @ $.06/lf	$ 1.50	---
	$ 32.10	---
15% O & P	4.82	
TOTAL ADDITION	$ 36.92	

	ADD	DEDUCT
X - SECTION 28 - RESILIENT FLOOR COVERING (Newell, Orr & Walsh, Inc.)		
1) Add 25 LF A.T.C. Base @ $.182/lf	$ 4.55	---
	$ 4.55	---
15% O & P	.68	
TOTAL ADDITION	$ 5.23	

Hopper
Reply
12/18
Jos

120-5.18-82

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 15, 1950

DEC 15 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

To Gen. File

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Miscellaneous Iron

We are sending you herewith four (4) prints each of the following Miscellaneous Iron shop drawings submitted by General Bronze Corporation and C. E. Halback & Company:

HMS 49-3, dated 11/27/50 - Wireway Covers in Booths
Elevation 62'-0"

HMS 49-4, " 11/24/50 - Wireway Covers in Booths
Elevation 70'-6"

HMS 52-1, " 12/13/50 - Steel Radiator Enclosures
4th Floor

Will you please return two (2) prints each of the above drawings marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL:eab

15 Headquarters Planning Unit 1950

RECEIVED
DEC 18 1950
United Nations Headquarters
W.K. Harrison - Director of Planning

12/15

120-5-18-8

cc: Harrison
McLeod
Zunser
Hopper
Healy
Van Name

15 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
N ew York 17, N.Y.

Re: Contract HQ 1/795 - Meeting Halls and
Covering Over East River Drive
Notification of Change No. 38 (Estimate Requested)
Proposed revisions to Stairs #46 and #47

Gentlemen:

Attached hereto is one copy of Notification of Change No. 38 (Estimate Requested) approved by James A. Dawson for the United Nations.

This approval is given for you to proceed with the work required by the modification with reference to the proposed revisions to Stairs #46 and #47.

It is understood that this approval does not include the cost of this change as indicated in the Notification of Change No. 38, which is solely an approximation. It is understood, also, that the actual price adjustment will be made as required by the terms of the contract.

Very truly yours,

James A. Dawson
Co-Ordinator of Construction

Enclosure
JZ:ml

120-5-18-8

cc: Harrison
Zunser
McLeod
Harris
Hopper
Healy
Van Name

15 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, N.Y.

Re: Contract HQ 1/75 - Meeting Halls and
Covering Over East River Drive
Finish Hardware

Gentlemen:

I have your letter dated 7 December 1950 transmitting three (3) copies of the Lockwood Hardware Manufacturing Company's Hardware Schedule, dated 11 September 1950, revised 6 December 1950, and requesting permission to enter into a subcontract, in accordance with this hardware schedule, in the amount of $25,960.21.

In our letter to you dated 27 April 1950, you were granted permission to enter into a subcontract with Lockwood for all of the Finish Hardware.

You are now further notified that the above schedule is hereby approved and you are authorized to enter into a subcontract with the Lockwood Hardware Manufacturing Company to furnish and install the hardware required by this schedule at the unit prices stipulated, for the total sum of $25,960.21. Returned herewith are two (2) copies of the Hardware Schedule.

Very truly yours,

James A. Dawson
Co-Ordinator of Construction

Enclosures - 2
JZ:ml

7

120-5-18-8

cc: Aussem Zunser
Nelson VanName
Weigel Ryer
Healy McSpedon
Harris
Hopper

15 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: HQ 1/75 Contract - Meeting Hall and Cover Over East River Drive Samples - Floor Hardener and Dustproofing Material

Gentlemen:

Reference is made to your letter of the 1st instant wherewith you transmitted for our comments and/or approval, samples in triplicate of "Ferricon" Metallic Floor Hardener, as manufactured by Truscon Laboratories, which you propose to furnish for certain finished floor surfaces of the Meeting Halls.

Please be advised that floor hardening, dustproofing material, of type and manufacture as exemplified by the samples here on hand, is approved for use as satisfying the applicable requirements of Part IV, Construction Trades Specifications, Section 4, paragraph 3, sub-paragraph (g).

This approval in no way relieves the Contractor of his responsibility for the satisfactory performance of the work in accord with the Specifications of the Contract Documents.

Returned herewith, marked "Approved", are two (2) of the samples submitted.

Very truly yours,

HBW

James A. Dawson
Co-Ordinator of Construction

HBW:eam

cc: Anssem Zunser
Nelson VanMame
Weigel Ryer
Healy McSpedon
Harris
Hopper

15 December 1950

Fuller-Turner-Malah-Slattery, Inc.
409 East 42 Street
New York 17, New York

Re: HC 1/75 Contract - Meeting Hall
and Dover Over East River Drive
Samples - Floor Hardener and
Dustproofing Material

Gentlemen:

Reference is made to your letter of the 1st instant wherewith you transmitted for our comments and/or approval, samples in triplicate of "Ferricon" Metallic Floor Hardener, as manufactured by Truscon Laboratories, which you propose to furnish for certain finished floor surfaces of the Meeting Hall.

Please be advised that floor hardening, dustproofing material, or type and manufacture as exemplified by the samples here on hand, is approved for use as satisfying the applicable requirements of Part IV, Construction Trades Specifications, Section 4, paragraph 3, sub-paragraph (g).

This approval in no way relieves the Contractor of his responsibility for the satisfactory performance of the work in accord with the Specifications of the Contract Documents.

Returned herewith, marked "Approved", are two (2) of the samples submitted.

Very truly yours,

James A. Dawson
Co-Ordinator of Construction

HDW:sam

120-5-18-8

cc: Zunser
Harris
Hopper
McGrath (Kennedy)

15 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, N.Y.

Re: Contract HQ 1/75 - Meeting Halls and
Covering Over East River Drive
Concrete Slabs

Gentlemen:

Enclosed, for your information and immediate comment, is a copy of letter from Madigan-Hyland, dated 12 December 1950, enclosing a partial summary of cylinder compression test reports for concrete for the slabs in the Meeting Hall, and stating that they are very much concerned about the low strengths and resulting quality of the concrete.

Very truly yours,

James A. Dawson
Co-Ordinator of Construction

Enclosure
JZ:ml

120-5-18-8

15 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - Contract HQ 1/75
Paving at the 29'-0" Level
Notification of Change No. 29

Gentlemen:

As of even date, we are forwarding you twelve (12) copies of our drawing No. L103, dated 14 December 1950. Please furnish for our consideration the prices based on the information indicated on this drawing.

You will note that this work has been approved under N. C. No. 29 as per our letter to you, dated 15 November 1950.

Very truly yours,

James A. Dawson
Co-Ordinator of Construction

JJHe:eam
cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
VanName
Ryer
McLeod

1-0-5-18-8

Fuller-Turner-Walsh-Slattery, Inc.
General Contractors
United Nations Permanent Headquarters

Re: C.O. #19

NOTIFICATION OF CHANGE

Date: **December 14, 1950**

TO: Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, New York

N. C. # **39** Building **Contract HQ 1/75 - Meeting Halls & Cover Over East River Drive**

Reference Information: **U. N. Dwgs. RA-6, 7, 8 & MH/CS-145, 147**

Description of Change: **Revisions to West Wall between Cols. 15 and 20A**

The above contemplated change affects the branches of the work indicated by X marks. There is shown below a quick estimate of the approximate cost of the change merely to indicate its magnitude and to assist the Owner in determining whether or not the change should be made.

( ) M-T-W-S Inc. Work:
( ) Structural Steel
X) Concrete Construction Work
( ) Concrete Slabs & Fireproofing
( ) Floor & Roof Fill
( ) Finish Cement Work
X) Masonry-Mortars
( ) Waterproofing (Membrane-Spandrel)
( ) Dampproofing (Mastic)
( ) Caulking
X) Cut Stonework
( ) Roofing (Built U.)
( ) Carpentry & Millwork
X) Ornamental Metal Work

X) Construction Insulation
( ) Metal Doors, Frames & Trim
( ) Roll-up Steel Doors
( ) Metal Toilet Enclosures
( ) Hollow Metal Partitions
( ) Marble Work
( ) Ceramic Tile
( ) Terrazzo Work
X) Furring & Lathing
X) Plastering
( ) Acoustical Treatment Sound Conditioning
X) Miscellaneous Iron
( ) Finish Hardware

X) Painting & Finish
( ) Venetian Type Blinds
X) Resilient Floor Covering
( ) Miscellaneous Accessories
( ) Heating, Ventilating & Air Conditioning
( ) Plumbing
( ) Sprinklers
( ) Electrical
( ) Sheet Metal Work
X) Glass & Glazing

The Approximate Total Cost of this Change is $ **(SEE ATTACHMENT**

and the Owner's immediate decision is required, avoiding a "Stop Order" of Field Operations and permitting the work to continue without interruption.

FULLER-TURNER-WALSH-SLATTERY, INC.

By_____ Date_____
Project Manager

The Above change will not be made and the work is to proceed in accordance with the existing Contract Requirements.

UNITED NATIONS HEADQUARTERS

By_____ Date_____

You are hereby instructed to proceed with the work in accordance with this N. C. and issue P.W.O.'s as required. Price Adjustments to be made under the Contract Terms.

UNITED NATIONS HEADQUARTERS

By J. M. Lawson Date 1/3/51

Fuller-Turner-Walsh-Slattery, Inc.
General Contractors
United Nations Permanent Headquarters

ATTACHMENT: For N. C. #39
Contract HQ 1/75 - Meeting Halls
(Change No. 19)

December 14, 1950

The Approximate Total Cost of this Change is: $4700.

Authorization given by U. N. letter dated 5/22/50 for Ornamental Metal Work and Miscellaneous Iron amounting to approximately $2200.

Authorization given by U. N. letter dated 5/10/50 for Concrete Construction amounting to approximately $100.

Authorization for proceeding with the remaining work requested by this N. C. amounting to approximately $2400.

Method of preparing this N. C. discussed with Mr. J. J. Healy on December 14, 1950.

120-5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 14, 1950

file

Mr. James A. Dawson
Co-Ordinator of Construction
U. N. Planning Office
405 E. 42nd St.
New York 17, N. Y.

Re: Meeting Halls & Covering over East River Drive - Contract HQ 1/75.

Dear Sir:

We are attaching hereto three (3) signed copies of Change Order #1, which is an addition to the contract of J. Harry Mc Nally Mason Corp., dated May 25, 1950 for Masonry Work, Meeting Halls & Covering over East River Drive, U. N. Permanent Headquarters, New York, in the amount of $55.41.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

H. A. Hiener
Office Manager

HAH:vh

enc.

12/14

FILE

-8-

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Re: Contract HQ 1/75 -- Meeting Halls and Covering over East River Drive
CHANGE NO. 160 - Miscellaneous Changes

References: (a) UN Drawings RA-1, RA-1A and RA-1B, dated December 6, 1950.
(b) Mr. James A. Dawson's letter of 7 December 1950 to F-T-W-S, Inc.

Dear Mr. Dawson:

On December 7, 1950 we received Reference (a) and on December 8, 1950 we received your letter, Reference (b), which reads as follows:

> "As of today's date, 7 December 1950, we are forwarding you fifteen (15) copies of the following drawings:
>
> RA-1, RA-1A and RA-1B, all dated 6 December 1950.
>
> These drawings have been prepared to amplify information released verbally to your Mr. C. Bartley as referred to in our letter dated 3 November 1950, reference Special Lighting Fixtures, and to amplify construction conditions.
>
> Proceed with the work shown thereon and submit for our consideration prices which may affect the Contract Price."

Under the authority and requirements of the contract, we hereby request that proper adjustment of the contract price and contract time be dealt with under the terms and conditions of the contract. This change will be analyzed with all interested subcontractors and detailed estimates will be submitted to you as quickly as possible. Definite extension of contract time for completion will be requested as soon as determination can be made of the effect of this change on the entire job progress.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan, Project Manager

MJG:JTB*eab

Hannegan
28 Mar. 51

OREGON 9-3950

file

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, New York

RE: CONTRACT HQ 1/75 - MEETING HALLS AND COVER OVER EAST RIVER DRIVE
ESTIMATE FOR CHANGE NO. 154
"Plumbing Changes to Expansion Joint Drainage"

References: a) United Nations Drawing SK-MH-P-7B-1, dated 10/30/50
b) " " Letter (Dawson) to FTWS dated 11/21/50

Dear Sir:

In accordance with the requirements and authority of Article 8(g) of our Contract HQ 1/75, we claim an increase in our total guaranteed maximum cost price in the amount of ONE HUNDRED EIGHTY FIVE DOLLARS AND SIXTEEN CENTS ($185.16) for those changes in plumbing work and sheet metal work listed herein which are required by the above "references".

The above price is broken down as follows:

I - SECTION B - PLUMBING WORK
(Eugene Duklauer, Inc.)

	Add
Plumbing changes to expansion joint drainage.....	$ 151.51

II - SECTION 10 - ROOFING & SHEET METAL WORK
(New York Roofing Company)

Changes in sheet metal work.

Solder, coal and acid.....	$ 2.00	
Field Labor.....	24.80	
6% Welf. & Pension.....	1.49	
	$28.29	
15% Overhead and Profit.....	4.24	
FOAB & UI:.....	1.12	
	$33.65.....	$ 33.65
TOTAL ADDITION - THIS CHANGE.....		$ 185.16

Attached are three copies of Eugene Duklauer's Estimate dated 11/30/50.

Rec'd 3/29/51
J.G.H.

Will you kindly issue a Change Order-Addition in the amount of $185.16 covering the revisions in work itemized above.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER:amc
attach.

EUGENE DUKLAUER INC.

ESTIMATE NO. Change #154

JOB Meeting Halls DATE 11/30/50

ARCHITECT U.N. FTWS DWG. NO. SHEET NO

DESCRIPTION
Plbg. Changes to Exp. Joint Drg.

QUANTITY	ITEM	PRICE	QUANTITY	ITEM	PRICE
	ADD				
	4x3 C.I. Y	2 28			
1	3	1 73			
2	3" 1/8 bends	1 72			
2	3" SW	3 62			
20	3" Pipe	1 9 36			
4	3" Galv. steel nipples	2 24			
2	3" " F.V.	8 20			
2	3" Gaskets	60			
4	3" Hangers	2 40			
40#	Lead	8 00			
1/5	Gas	60			
#	Oakum	80			
	Labor 1 1/2 day	6 3 00			
	Foreman 1 1/2 hr.	5 28			
	Welfare etc. .11	7 51			
	Contr Lia. .0034	51			
	Sales Tax 2%	1 03			
		1 2 8 85			
	OH&P 15%	1 9 25			
	FOAB etc. .05	3 41			
		1 5 1 51			

RECEIVED

DEC 1 1950

FULLER - TURNER - WALSH - SLATTERY
INCORPORATED

Kennedy
Pls see me w/this
Pls see me
Reese

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 14, 1950

Contract #169

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, N. Y.

file

Re: Damage to F.D. R. Drive

Dear Mr. Dawson:

Attached hereto is a copy of Burns' Guard Howe's report of December 10, 1950 regarding damage to lights and the underside of the concrete cover over the northbound lane of F.D.R. Drive caused by the Borough President's paving contractor.

Your Mr. Kennedy and our Mr. Plude have inspected the area mentioned and have found the damage to be as reported. They warned the contractor to be careful. He admitted causing the damage and is willing to repair it.

We are notifying you so that you can take the matter up with the Borough President, if you deem it advisable.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER:ar
Enclosure

Mr. Jerry Grace Gen. Superintendent for Moscali promised Messrs. McGrath, Plude & myself that he would repair the damage to the Service Drive cover caused by his travel.
Damage consists of 6± chips in fireproofing 3 or 4 scratched paint areas & some broken electric lights.
I do not think it necessary to notify the B.P.M.
W.B. Kennedy
12/15

15 1950 Headquarters Planning Office

COPY OF GUARD'S REPORT

December 10, 1950

On a tour of inspection of area along F.D. R. Drive it was noticed that there are 16 lights damaged along the future north bound lane of F.D.R. Drive near Col. 16 and 39 approximately between 44th and 46th Streets. Also the underside of the concrete cover in this section is chipped in various places.

This damage might have been caused by the crane working along this road.

/s/ Guard Howe

YDR

120-5-18-82

copy to Heller Tex
Pat for immediate attention
Reed

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
Secretariat Building
New York, N. Y.

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive - Concrete Cylinder Tests.

Dear Mr. Dawson:

Several times recently we have called to the attention of Brennan & Sloan, Inc. and Knickerbocker Construction Corporation the fact that concrete cylinder test reports for the 28 day break have shown strengths considerably below the designed strengths.

We are attaching hereto a copy of Mr. F. P. Sloan's letter of December 12, 1950 in which he states that Brennan and Sloan - Knickerbocker " have no question as to the proper strength of the concrete in the structure but the paper work does not reflect that fact." He points out that the irregularities are appearing only in the Meeting Halls test reports and that, in his opinion, the cylinders are not being properly made and stored.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese.

C. E. Reese
Project Engineer

CER:ar
Enclosure

Pr 12/19

BRENNAN & SLOAN, INCORPORATED
AND
KNICKERBOCKER CONSTRUCTION CORPORATION
NEW YORK 17, N. Y.

December 12, 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, New York

Re: Meeting Halls & F.D. R. Drive

Gentlemen:

We wish to call your attention for the third time to the fact that concrete cylinder test reports for the Meeting Hall job are currently not representative of the concrete being poured.

Reports for the Secretariat, South Garage, and North Garage jobs show breaks well above contract requirements but irregularities are appearing in the Meeting Hall test reports. In our opinion the reports indicate that cylinders are not being properly made and stored.

On November 16th the writer telephoned Mr. Matt Grogan that there was no standard storage box for safekeeping and initial curing of cylinders. At a later job meeting we warned that seven day tests then current indicated low 28 day tests to come.

Your testing engineers inspect the concrete aggregates, design the mix, varying the proportions of fine and coarse aggregates and the quantity of cement per cubic yard. They also supervise the mixing.

There is absolutely no reason why design strengths should not be consistently exceeded if the ASTM standards are followed as to sampling, making cylinders, storing at the job at proper temperatures, removing to the laboratory at the proper time, storing as specified, capping and breaking. Variations from the ASTM standards in any one of these operations will result in low strengths.

We have no questions as to the proper strength of the concrete in the structure but the paper work does not reflect that fact.

Yours very truly,

BRENNAN & SLOAN, INCORPORATED AND
KNICKERBOCKER CONXTRUCTION CORPORATION

F. P. Sloan

Hopper
Neely
12/14
Sol

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

Lobrano. Fica

December 14, 1950

RECEIVED
DEC 14 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Miscellaneous Iron

We are sending you herewith four (4) prints of the following Miscellaneous Iron shop drawing submitted by General Bronze Corporation and C. E. Halback & Company:

HMS 12-2B South, revised 11/29/50 - Vertical and Ceiling Expansion Joints, 2nd Basement So.

Will you please return two (2) prints of the above drawing marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

RECEIVED
DEC 15 1950
United Nations Headquarters
W.K. Harrison-Director of Planning

12/14

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 14, 1950

RE
DEC 14 1950
United
(Co-ordinator of Construction)

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print each of the following Miscellaneous Iron shop drawings as approved for field distribution:

HMS 51-1,	revised	12/8/50	- F.S.D. of Steel Framing for Booths
51-2,	"	"	- Supports for Booth Front Conf.Rm.#1
51-3,	"	"	- Steel Framing for Booths " " #3
51-4,	"	"	- " " " " " " #2
12-2B No."		11/29/50	- Vertical & Ceiling Expansion Joints 2nd Basment (North Half)
12-1B So.No.	rev. "		- Vertical & Ceiling Expansion Joints 1st Basement
31-1,	revised	11/27/50	- Wire Work between Plenum & F.A.I. Col. X8 to X10.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL*eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print each of the following Miscellaneous Iron shop drawings as approved for field distribution:

HMS 51-1, revised 12/8/50 - F.S.D. of Steel Framing for Booths
51-2, " " - Supports for Booth Front Conf.Rm.#1
51-3, " " - Steel Framing for Booths " " #3
51-4, " " - " " " " " " #2
12-2B No." 11/29/50- Vertical & Ceiling Expansion Joints 2nd Basment (North Half)
12-1B So.No. rev. " - Vertical & Ceiling Expansion Joints 1st Basement
31-1, revised 11/27/50- Wire Work between Plenum & F.A.I. Col. X8 to X10.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print each of the following Miscellaneous Iron shop drawings as approved for field distribution:

HMS 51-1,	revised 12/8/50	-	F.S.D. of Steel Framing for Booths
51-2,	" "	-	Supports for Booth Front Conf.Rm.#1
51-3,	" "	-	Steel Framing for Booths " " #3
51-4,	" "	-	" " " " " " #2
12-2B No."	11/29/50	-	Vertical & Ceiling Expansion Joints 2nd Basment (North Half)
12-1B So.No. rev. "		-	Vertical & Ceiling Expansion Joints 1st Basement
31-1,	revised 11/27/50	-	Wire Work between Plenum & F.A.I. Col. X8 to X10.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL#eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print each of the following Miscellaneous Iron shop drawings as approved for field distribution:

HMS 51-1,	revised	12/8/50	- F.E.D. of Steel Framing for Booths
51-2,	"	"	- Supports for Booth Front Conf.Rm.#1
51-3,	"	"	- Steel Framing for Booths " " #3
51-4,	"	"	- " " " " " " #2
12-2B No."		11/29/50	- Vertical & Ceiling Expansion Joints 2nd Basment (North Half)
12-1B So.No. rev. "			- Vertical & Ceiling Expansion Joints 1st Basement
31-1,	revised	11/27/50	- Wire Work between Plenum & F.A.I. Col. X8 to X10.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL:eab

120-5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 14, 1950

RECEIVED
DEC 15 1950
United Nations Headquarters
JAMES A. DAWSON
Co-ordinator of Construction

Mr. James A.Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS-11-1, revised 11/28/50 - Steel Saddles for Openings 1B127 and 1B130

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

15 1950
Headquarters Planning Office

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

NEW YORK

December 14, 1950

Mr. James A.Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS-11-1, revised 11/28/50 - Steel Saddles for Openings 1B127 and 1B130

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS-11-1, revised 11/28/50 - Steel Saddles for Openings 1B127 and 1B130

(General Bronze Corporation and G. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
Project Engineer

FMcL:eab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 14, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS-11-1, revised 11/28/50 - Steel Saddles for Openings 1B127 and 1B130

(General Bronze Corporation and G. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese

C. E. Reese
Project Engineer

FWcL*eab

120-5-18-8

14 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over
East River Drive - HQ 1/75
Ornamental Metal

Gentlemen:

We are returning drawings GBM-36, GBM-37, and GBM-38; GBM36, marked "Approved"; GBM-37 and GBM-38, marked "Approved as Noted".

These drawings are approved and approved as noted with the proviso that the load test which will be conducted at the plant of the General Bronze Corporation will show that the mullions are strong enough to withstand the superimposed loads, as per the discussion between our structural consultant, Mr. Walthers and Mr. W. Engert of the General Bronze Corporation.

Please notify us when this test will be conducted so that the structural representative and our own men will be present.

Very truly yours,

JJHe:eam

James A. Dawson
Co-Ordinator of Construction

cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
VanName
Ryer
Walthers (Madigan-Hyland)

120-5-18-8

14 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East
River Drive - Contract HQ 1/75
Electrical - Special Lighting

Gentlemen:

As per our transmittal of 20 November 1950 we forwarded you fifteen (15) copies of our drawings MH-L1 to 6 inclusive, the special lighting drawings. You will see a note on Drawing L5, "See later drawing for design of lighting in this room". You are to disregard this note and proceed with the lighting as indicated on this drawing for the Trusteeship Council Chamber.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JZ/le:eam

cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
Dawson
VanName
Ryer
Seelman
Hannegan
S & H (2)

File -82

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, N. Y.

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive - CHANGE No. 158 - Changes in Glass Thickness

Dear Mr. Dawson:

On Wednesday, December 6, 1950, your Mr. J. J. Healy held a meeting at United Nations Planning Headquarters at which representatives of the Abbott Glass Company, General Bronze Corporation and Fuller-Turner-Walsh-Slattery, Incorporated, were present. This meeting was called to discuss probable changes in the thickness of the glass for the Meeting Hall windows. At the meeting, Mr. Healy handed to us black and white prints of United Nations drawing SK-304 - "Elevations", which had been marked in blue crayon to show the revised thickness of glass which you would probably require. The notations on this drawing required revisions in the glass as shown on the attached sheet dated December 13, 1950 and entitled "Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive - Change No. 158 - Changes in Glass Thickness."

We were also advised that the stainless steel glazing channels are to be omitted and that all windows are to be glazed with glazing compound. Since the 3/4" wide rabbets which had been provided for stainless steel glazing channels are too wide for putty glazing it will be necessary to reduce the width of each rabbet by installing an aluminum filler on the face of each removable glass stop. These fillers are to be of sufficient thickness to reduce the rabbet to such a width that there will be 1/8" of glazing compound on each side of the glass.

We pointed out to Mr. Healy that all of the glass which had been ordered for exterior glazing in accordance with previous instructions had been delivered to Abbott Glass Company's shop or was in the process of being trucked there from the steamship line. There is one exception to the previous statement, namely, the Solex Glass which had been ordered for the south elevation. This glass had been manufactured and crated ready for shipment.

continued on page 2 .....

Prices for this Change were presented informally to your representatives on Friday, December 8, 1950. Revised figures were given to Mr. M. Harris by phone on Tuesday, December 12, 1950. At the meeting of your representatives with our Operating Committee on Tuesday, December 12, 1950, Mr. Joseph Zunser instructed us to proceed with this change.

A question arose whether the United Nations wished to take for stock the 1/4" polished plate and Solex glass which is now surplus due to this change. On Wednesday, December 13, 1950, Mr. M. Harris advised us that the United Nations did not want this glass and we are to have the Abbott Glass Company take it for their own use. The credit for these items will be included in our estimate for this Change.

Under the authority and requirements of the contract, we hereby request that proper adjustment of the contract price and contract time for completion be made on account of the above change, and that such adjustment be dealt with under the terms and conditions of the contract. This change will be analyzed with all interested subcontractors and detailed estimates will be submitted to you as quickly as possible. Definite extension of contract time for completion will be requested as soon as determination can be made of the effect of this change on the entire job progress.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER:ar

CONTRACT HQ 1/75 - MEETING HALLS
AND COVER OVER EAST RIVER DRIVE
CHANGE NO. 158 -
CHANGES IN GLASS THICKNESS Dec. 13, 1950

A. Elevation # 1 - East Elevation

(1) Windows from Elevation 29'-0" to 53'-0"

(a) Door and transom lights to remain 1/4" polished plate.
(b) Large lower lights to be changed from 1/4" polished plate to 3/8" polished plate.
(c) Upper lights to remain 1/4" polished plate

(2) Windows from Elevation 53'-0" to 83'-0"

(a) All lights to remain 1/4" polished plate.

(3) Windows at Elevation 83'-0" (4th Floor)

(a) Door and transom lights to remain 1/4" polished plate.
(b) All other lights to be changed from 1/4" polished plate to 3/8" polished plate.

B. Elevation # 2 - South Elevation

(1) Window and door lights at Elevation 29'-0" to remain 1/4" polished plate.

(2) Window and door lights at Elevation 41'-0" to remain 1/4" polished plate.

(3) Lights between Column Lines S and T at Elevations 53'-0" and 68'-4" to remain 1/4" polished plate.

(4) Window from Elevation 53'-0" to 83'-0" between Column Lines T and Y.

(a) Door lights to be changed from 1/4" Solex to 1/4" polished plate.
(b) Two lower rows of large lights to be changed from 1/4" Solex to 3/8" polished plate.
(c) Upper row of lights (including those for hopper sash) to be changed from 1/4" Solex to 1/4" polished plate.

(5) Windows at Elevation 83'-0"

All lights to be changed from 1/4" polished plate to 3/8" polished plate.

C. Elevation # 3 - North Elevation

(1) Elevation 29'-0" - Window and door lights to remain 1/4" polished plate

(2) Elevation 41'-0" - Small windows
Lights to remain 1/4" polished plate.

(3) Elevation 53'-0" to 83'-0" - Large window

(a) Door lights to remain 1/4 " polished plate.
(b) All window lights to be changed from 1/4" polished plate to 3/8" polished plate.

(4) Window at Neck - (North Face)

(a) Lights at Elevation 41'-0" to remain 3/8" polished plate
(b) Large lights at Elevation 53'-0" to be changed from 3/8" polished plate to 1/2" polished plate.
(c) Door and transom lights at Elevation 53'-0" to remain 1/4" polished plate.
(d) Large lights at Elevation 68'-4" to be changed from 1/4" polished plate to 3/8" polished plate.
(e) All spandrel lights to remain 1/4" Pilkington Georgian polished wire glass.

(5) Windows at Elevation 83'-0"

(a) All lights to be changed from 1/4" polished plate to 3/8" polished plate.

D. Elevation # 4 - West Elevation

(1) At Elevation 41'-0"

(a) Door lights to remain 1/4" polished plate.
(b) Large lights to remain 3/8" polished plate.
(c) Spandrel lights (over) to remain 1/4" Pilkington Georgian polished wire glass.

(2) At Elevation 53'-0"

(a) Large lights to be changed from 3/8" polished plate to 1/2" polished plate.
(b) Spandrel lights (over) to remain 1/4" polished plate.

D. Elevation # 4 - West Elevation

(3) At Elevation 68'-4"

(a) Large lights to be changed from 3/8" polished plate to 1/2" polished plate.

(4) At Elevation 83'-0"

(a) Door and transom lights to remain 1/4" polished plate.
(b) Large lights to be changed from 1/4" polished plate to 3/8" polished plate.

E. Elevation # 5 - South Elevation of Neck

(a) Lights at Elevation 41'-0" to remain 3/8" polished plate.
(b) Spandrel lights (over) to remain 1/4" Pilkington Georgian polished wire glass.
(c) Large lights at Elevation 53'-0" to be changed from 3/8" polished plate to 1/2" polished plate.
(d) Spandrel lights (over) to remain 1/4" polished plate.
(e) Large lights at Elevation 68'-4" to be changed from 3/8" polished plate to 1/2" polished plate.

120-5-18-8

OREGON 9-3950

Pax Hear
Conforms to what they
Phone has made to his conducting the
would be in metal
will on pls
prepare rep

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 13, 1950

Mr. Joseph Zunser,
Assistant Coordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Zunser: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Drive
Contract HQ 1/82 - General Assembly & North Parking Garage
Metal Doors, Frames and Trim

You are aware of the fact that Atlantic Metal Products, Inc. is having great difficulties in obtaining steel sheets for making the steel bucks and hollow metal doors for the Meeting Halls, North Parking Garage and General Assembly. This situation is becoming very critical.

We are attaching hereto a copy of Atlantic Metal Products' (Mr. Alfred Held, President) letter of December 4, 1950 in which he suggests the use of hot rolled pickled steel, in lieu of the cold rolled steel you specified, because the hot rolled pickled sheets are more available. In a previous letter he had informed us that "during the last two or three years the mills have only taken a minimum of cold rolled sheet steel orders, but have accepted hot rolled pickled sheet steel orders".

Mr. Held's letter mentions the acceptability of the hot rolled pickled steel for some of the finest building projects. He has also told us that it is used for almost all of the jobs that Atlantic gets.

A check which the writer made with Bethlehem some months ago when we were contemplating using hot rolled pickled sheets during the trucking strike bears out Mr. Held's statement that the price for the two classes of sheets is identical.

In view of the present shortages of sheet steel and the particular difficulty in obtaining cold rolled sheets, it appears to us that the wisest thing to do would be to approve the use of hot rolled pickled sheets if they are obtainable. Will you please advise us promptly whether this substitution is satisfactory to you with no change in our contract price.

18 1950 Headquarters Planning Unit

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER:eab

12/18

ATLANTIC
METAL PRODUCTS INC.

5-15 48th Avenue, Long Island City 1, N.Y.

December 4th, 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd St.
New York, N. Y.

Att: Mr. M. J. Grogan, Project Engineer

Gentlemen:

After discussing our steel situation with your Messrs. Grogan and Reese over the telephone today, may we suggest that it might be possible for your organization to get an allotment of hot rolled pickled steel sheets in lieu of cold rolled sheets as specified for the United Nations buildings.

Hot rolled pickled sheets are manufactured by all the larger mills, and have been acceptable for the manufacture of hollow metal doors and frames for some of the finest building projects in our city and throughout the country.

Today many more hot rolled pickled sheets are available than cold rolled sheets, due to circumstances we are not able to explain. We feel sure, however, that hot rolled pickled sheets, if used for the steel doors and bucks on the United Nations buildings, would make an excellent job, and would be acceptable to the architects and everyone else concerned.

The price for the two classes of sheets is identical, and there would be no money saving if the substitution were made. If hot rolled pickled sheets are acceptable, we thought it might be possible for you to get some mill to accept our order for this material and give us an immediate delivery of the hot rolled pickled steel sheets in order to keep the job going.

Very truly yours,

ATLANTIC METAL PRODUCTS, INC.

/s/ Alfred Held
President

AH:EG

Copy

120-5-11-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 13, 1950

O.K.

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Exit Type Light Fixture Sample

Dear Sir:

We are submitting herewith for approval one sample of the McPhilpen Mfg. Co. Sample Catalog No. 545H, recessed mounted exit fixture with a cast hinged frame as shown on the Drawing No. 54-1123. This is being furnished under the Electrical subcontract of Fischbach & Moore, Inc. The above mentioned drawing is being held up pending submission of this sample. We therefore request you review the above sample and return three (3) copies of this letter together with your approval and/or comments. We also request returneof three (3) copies of the above drawing. Fischbach and Moore, Inc. also advise they would like to have this sample back in order that it may be used in the construction of the building.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER:WWS:bc

12/18

18 DEC 1950
Headquarters Planning

120-5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

(6)

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Furring and Lathing

Sections D-D and E-E on drawing RA-6, revised 19 June 1950, faintly indicate a plaster stop where the plaster on the block wall finishes against the underside of the plate of the expansion joint assembly attached to that wall.

This letter confirms Mr. W. Cunningham's conversation with Mr. J. J. Healy on December 7, 1950, during which Mr. Healy advised that this plaster stop will not be required. Mr. Healy further advised that no plaster stops will be required at any location in the building where a similar condition occurs.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER*eab

~~Shop Dwg. No.~~ H-MS 121F.
returned 11 Dec. 1950
Resubmit

Hopper
Dealey
12/14
Lost

120-5-18-82

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 13, 1950

RECEIVED
DEC 14 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

To Bro. Fick

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Miscellaneous Iron

We are sending you herewith four (4) prints of the following Miscellaneous Iron shop drawing submitted by General Bronze Corporation and C. E. Halback & Company:

HMS-49-2, revised 12/8/50 - Wireway Covers in Booths Elevation 41'-0"

Will you please return two (2) prints of the above drawing marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL:eab

RECEIVED
DEC 15 1950
United Nations Headquarters
W.K. Harrison-Director of Planning

12/14

Sect
Hopper - Rumpelter
Kanegan
12/14
EJS

120-3-11-12

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

RECEIVED
DEC 14 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

December 13, 1950

Gen Files

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Heating, Ventilating and Air Conditioning
Ductwork Shop Drawings

Dear Sir:

We are submitting herewith six (6) copies of the National Sheet Metal Works Inc. Drawings for Ductwork being furnished under the Heating, Ventilating and Air Conditioning subcontract of Kerby Saunders, Inc.

Drawing No.	1BS-13,	Ductwork in Fan Room No. 7.
" "	1N-6,	Ductwork 1st floor North, Cols. 18 to 20 & V to Y.

We request the return of three (3) copies of each of the above drawings together with your approval and/or comments at your earliest convenience.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

Ret'd 26 Dec 1950

C. E. Reese

C. E. Reese
Project Engineer

CER:WWS:bc

12/14

120-5-18-8

Sent Hopper-Seelman Hannegan 12/18 LS

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

Gen File

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Electrical - Trumbull Circuit Breaker Switchboards

Dear Sir:

We are resubmitting herewith six (6) copies of each of the following Trumbull Electric Mfg. Co. Drawings for the switchboards which they propose to furnish under the Electrical subcontract of Fischbach & Moore, Inc.

Drawing No. ENY-128-17, Revision No. 2 to Main Switchboard Section D.
" " ENY-128-18, Revision No. 2 to Main Switchboard Sections B&C.
" " ENY-128-19, Revision No. 2 to Main Switchboard Section A.

Please review the above drawings and return three (3) copies with your approval and/or comments at your earliest convenience.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER:WWS:bc

18 Headquarters Planning Office 1950

RECEIVED
DEC 18 1950
United Nations Headquarters
W.K. Harrison-Director of Planning

ISSUANCE OF DRAWINGS

OFFICE COPY

28 Dec. 1950

Meeting Halls

Fuller-Turner-Walsh-Slattery, Inc.

403 E. 42nd St.

Mr. Blumquist

3 each of:

ENY-128-17 27Nov1950 Cir. Breaker Swbd. Sect. D

approved 27Dec.1950 JTA

ENY-128-18 27Nov1950 Sect. B and C

approved 27Dec.1950 JTA

ENY-128-19 27Nov1950 Cir. Breaker Swbd Sect. A

approved 27Dec.1950JTA

submitted by Fischbach and Moore, Inc.

Hopper
Healy
12/13
JWJ

120-5-18-84

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 13, 1950

DEC 13 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

To Gen. File

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Finish Hardware

We are sending you herewith four (4) prints each of the following Push and Pull shop drawings submitted by Lockwood Hardware Mfg. Company (Independent Lock Co.):

30142, dated 12/5/50 - Special Push-Pulls S448 for Flush Wood and Hollow Metal Doors 1-3/4" Thick

30146, " " - Special Push-Pulls S452 for 2¼" Stile Aluminum Doors 1-3/4" Thick

Please note that for 2¼" thick aluminum doors furnished by General Bronze Type S452 can be used if the through bolt is extended.

Will you please return two (2) prints each of the above drawings marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese

C. E. Reese
Project Engineer

FMcL*eab

12/13

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 13, 1950

RECEIVED
DEC 14 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Metal Doors, Frames and Trim shop drawing as approved for field distribution:

Sheet 28, revised 10/27/50 - 4-sided Frame Receiving Records and Control Room

(Atlantic Metal Products, Inc.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcI*eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Metal Doors, Frames and Trim shop drawing as approved for field distribution:

Sheet 28, revised 10/27/50 - 4-sided Frame Receiving Records and Control Room

(Atlantic Metal Products, Inc.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL:eab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Metal Doors, Frames and Trim shop drawing as approved for field distribution:

Sheet 28, revised 10/27/50 - 4-sided Frame Receiving Records and Control Room

(Atlantic Metal Products, Inc.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL:eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Approved Shop Drawings

We are sending you herewith one (1) print of the following Metal Doors, Frames and Trim shop drawing as approved for field distribution:

Sheet 28, revised 10/27/50 - 4-sided Frame Receiving Records and Control Room

(Atlantic Metal Products, Inc.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL:eab

120-5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson:

Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS 12-24, revised 11/25/50 - Expansion Joints at Roof Elev. plus 94'-1" and 105'-5½"

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
Project Engineer

FMCL:eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson:

Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS 12-24, revised 11/25/50 - Expansion Joints at Roof Elev. plus 94'-1" and 105'-5½"

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMCLreab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

HMS 12-24, revised 11/25/50 - Expansion Joints at Roof Elev. plus 94'-1" and 105'-5½"

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMCLweab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 13, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Approved Shop Drawings

We are sending you herewith one (1) print of the following Miscellaneous Iron shop drawing as approved for field distribution:

MMS 12-24, revised 11/25/50 - Expansion Joints at Roof Elev. plus 94'-1" and 105'-5½"

(General Bronze Corporation and C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FWL:eab

120-5-18-8

cc: Harrison
McLeod
Zunser
Van Name
Hopper
Healy

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, N.Y.

Re: Contract HQ 1/75 - Meeting Halls and
Covering Over East River Drive
Notification of Change No. 37 (Change No. 1)
Architectural Drawings - Revision #1
Plumbing Drawings - Revision #1
General Revisions in all above drawing lists
(exclusive of Heating, Ventilating and Air Conditioning (See Partial Estimate No. 1 for Change No. 1)

Gentlemen:

Attached hereto is one copy of Notification of Change No. 37 (Change No. 1) approved by Joseph Zunser for the United Nations.

This approval is given expressly for the purpose of permitting you to proceed with the work except for those items known to be in the process of revision such as the glass and glazing item, which will be revised since we are contemplating glazing with the glazing compound.

It is understood that this approval does not include the cost of this change as indicated in the Notification of Change No. 37, which is solely an approximation. It is understood, also, that the actual price adjustment will be made as required by the terms of the contract.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

Enclosure

JZ:ml

120-5-18-8

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - Contract HQ 1/75
Glass and Glazing

Gentlemen:

Please refer to your letter of 16 November 1950, wherein you request specific instructions as to how the windows are to be glazed.

Since the receipt of this letter, you have received verbal and written instructions that you are to glaze the windows with glazing compound.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JZ:He:eam
cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
VanName
Dawson

120-5-18-8

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - HQ 1/75 Contract Concrete Work

Gentlemen:

On 13 December 1950 we forwarded you six (6) copies of Drawing SK-145, showing depressions in the floor at the bars in the North and South Delegates' Lounges, "The Interior Drawing".

Before proceeding with any of the work shown on the drawing, furnish for our consideration prices which may affect the Contract Price. We will advise you how to proceed after having received the quotation.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JJHe:~~eam~~
cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
Dawson
VanName
Ryer
Hannegan

120-5-18-8
✓

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - Contract HQ 1/75 Glass and Glazing and Ornamental Metal - Exterior Windows

Gentlemen:

Please refer to your letter of 29 November 1950, wherein is contained certain information reference the cost of supplying 1/8" and 1/4" filler bars in the glazing rabbets, and the cost of glazing with stainless steel glazing channels.

Please be advised that all of this information is voided as per our recent discussion with your Messrs. C. E. Reese and W. Cunningham, and the representatives of the Abbott Glass Company and the General Bronze Corporation.

A breakdown, based on the revised thickness of the glass and flat bar fillers, will be resubmitted as per the discussion at the Contractor's Meeting of 12 December 1950.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JZ:He:eam
cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
Dawson
VanName
McLeod

120-5-18-8

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - Contract HQ 1/75
Simultaneous Interpretation Booth Shelves

Gentlemen:

On 12 December 1950 we forwarded you six (6) copies of Drawing SK-363, dated 12 December 1950.

Before proceeding with the installation of any of the work shown on this drawing, furnish for our consideration prices which may affect the Contract Price due to the revision. After we will have received your quotation, we will advise you how to proceed.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JZ:Hc:cam
cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
VanName
Dawson
Ryer

120-5-18-8

13 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42 Street
New York 17, New York

Re: Meeting Hall and Cover Over East River Drive - Contract HQ 1/75 Heating, Ventilating and Air Conditioning - Electric - Plumbing

Gentlemen:

On 13 December 1950, under separate cover, we forwarded you fifteen (15) copies of each of the following drawings, together with twenty-five (25) copies of Addendum No.4 to Part V, Section B, Plumbing Work:

SK-MH-P-8B-1, dated 27 November 1950
SK-MH-E-24P-1, dated 13 November 1950
SK-MH-H-21-1, dated 27 November 1950

Before proceeding with any of the work contained in the Specification or indicated on the drawings, furnish for our consideration prices which may affect the Contract Price. We shall instruct you how to proceed after having received your price.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

JJHe:eam

cc: Aussem
Nelson
Weigel
Healy
Harris
Hopper
Zunser
Dawson
VanName
Hannegan
Seelman
Rumpeltin
S & H (2)
Ryer

120 - 5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 12, 1950

file

Mr. James A. Dawson
Co-Ordinator of Construction
U. N. Planning Office
405 E. 42nd St.
New York 17, N. Y.

Re: Meeting Halls and Covering over East River Drive - Contract HQ 1/75.

Dear Sir:

We are attaching hereto three (3) signed copies of Change Order #9, issued to Kerby Saunders, Inc., which is an addition to their contract dated July 10, 1950 for Heating, Ventilating & Air Conditioning, Meeting Halls & Covering over East River Drive, U. N. Permanent Headquarters, New York, in the amount of $1,573.56.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

H. A. Hiener
Office Manager

HAH:vh

enc.

12/12

120-5-18-8

OREGON 9-3950

copy to Mr Dawson
copy to Mr Bass
copy to Mr Harris
copy to Walter Hopper (please see me about this)

14 Dec 50

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 12, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
U. N. Planning Office
405 E. 42nd St.
New York 17, N. Y.

Re: Meeting Halls - Contract HQ 1/75.

Dear Sir:

Our field forces find upon inspection that the stone facing of the Meeting Halls on the north elevation at the 53' level, northeast corner, was damaged at the time of the wind storm on November 25th.

The second course of ashlar above the bond stone is damaged at the 2nd, 3rd and 10th stone from the east corner.

This damage was caused by the hanging scaffold rubbing and striking against the stone during the storm.

We would suggest that this matter be taken up with the insurance company immediately and instructions issued regarding any changes you may wish in this work.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

H. A. Hiener
Office Manager

HAH:vh

enc.

12/12

120-5-18-8

Mr. McLeod

UNITED NATIONS NATIONS UNIES

NEW YORK

CABLE ADDRESS · UNATIONS NEWYORK · ADRESSE TELEGRAPHIQUE

FULLER TURNER WALSH SLATTERY, INC.

FILE NO.:

December 12, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
U.N. Planning Office
New York 17, N.Y.

Re: Meeting Halls - Contract HQ 1/75.

Dear Sir:

Our field forces find upon inspection that the stone facing of the Meeting Halls on the north elevation at the 53' level, northeast corner, was damaged at the time of the wind storm on November 25th.

The second course of ashlar above the bond stone is damaged at the 2nd, 3rd and 10th stone from the east corner.

This damage was caused by the hanging scaffold rubbing and striking against the stone during the storm.

We would suggest that this matter be taken up with the insurance company immediately and instructions issued regarding any changes you may wish in this work.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

/s/ H.A.Hiener
H.A. Hiener
Office Manager

HAH:vh

enc.

COPY

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 12, 1950

RECEIVED
DEC 13 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Construction & Sound Conditioning Insulation Samples

We are sending you herewith two (2) samples each of the following insulation materials submitted by Jeremiah Burns, Inc:

1. Full Thik (3" Plus) Johns-Manville Rock Wood Batt 3 - $\frac{1}{4}$ lb. Density proposed for use over metal lath hung ceiling between beams over F.D.R. Drive. EAST RIVER
2. 2" Johns-Manville Rock Wool Blanket $3\frac{1}{2}$ lb. Density proposed for use back of furring and lathing in Booth partition walls.

Kindly return one (1) sample each of the above marked with your approval and/or recommendations.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL*eab

RECEIVED
DEC 15 1950
United Nations Headquarters
W.K. Harrison-Director of Planning
12/13

120-3-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 12, 1950

RECEIVED
DEC 12 1950
United Nations Headquarters
JAMES A. DAWSON
Co-ordinator of Construction

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Metal Doors, Frames and Trim

We are sending you herewith four (4) prints each of the following Metal Doors, Frames and Trim shop drawings submitted by Atlantic Metal Products:

D-35, dated 12/7/50 - Plan of Blind Pockets along East Wall Briefing Room 109, Office 303, ~~Lounges 322 & 341~~ A-113 See 4-4

D-36, " " - Plan of Blind Pockets along East Wall (Offices 132, 133, 134, 152, 153 & 154- Details of Blind Pockets See Dwg A-118. A-113 See 4-4

Not Checked.

by End of year Jan 12, 1951

Please note that none of the blind pockets shown on above drawings were included in Atlantic Metal Products, Inc. subcontract. Since immediate fabrication of these pockets is required for orderly job progress, we request that you check the drawings immediately and return two (2) prints each marked with your approval or corrections.

We will submit the change in cost at a later date.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

See 4-4 typical for Rm 109 & 303.
Office Windows East Elev See Dwg A-118
1/11
Show Details of Office Windows E. Elev.

RECEIVED
DEC 15 1950
United Nations Headquarters
W.K. Harrison-Director of Planning

120-5-18-8

cc: Harrison
McLeod
Zunser
Van Name
Healy
Hopper

12 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, N.Y.

Re: Contract HQ 1/75 - Meeting Halls and
Covering Over East River Drive
Notification of Change No. 30 (Change No. 135)
Concrete Foundations for Refrigeration Equipment

Gentlemen:

Attached hereto is one copy of Notification of Change No. 22 (Change No. 135) approved by Joseph Zunser for the United Nations.

This approval is given for you to proceed with the work required by the modification with reference to the concrete foundations for refrigeration equipment, except that Alternate No. 1 - Furnish and Install Angles - is to be omitted.

It is understood that this approval does not include the cost of this change as indicated in the Notification of Change No. 22, which is solely an approximation. It is understood, also, that the actual price adjustment will be made as required by the terms of the contract.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

Enclosure
JZ:ml

120-5-18-8

cc: Dawson
Zunser
Hopper
Hannegan
Rumpeltin
Aussem
Healy
Van Name
Ryer

12 December 1950

Fuller-Turner-Walsh-Slattery, Inc.
403 East 42nd Street
New York 17, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive - Heating, Ventilating And Air Conditioning

Gentlemen:

We are forwarding herewith three (3) copies of revised front page to be inserted in your copies of the Warren Webster & Company Folder covering Bulletins B-705-5A, B-702D, B-712B and B-709A, transmitted to you as of 20 November 1950.

This revision is made to clarify the original front page of the Folder submitted by the Warren Webster Company, referring to Radiator Valves for radiators, Thermostatic Traps, Float and Thermostatic Traps for heating coils, and Strainers for Float and Thermostatic Traps.

Very truly yours,

Joseph Zunser
Assistant Co-Ordinator of Construction

Enclosures - 3

SSR:JJHa:mj

UNITED NATIONS NATIONS UNIES

NEW YORK

CABLE ADDRESS · UNATIONS NEWYORK · ADRESSE TELEGRAPHIQUE

FILE NO.:

MEETING HALLS.

Warren Webster & Co. material will be used according to this schedule:

Bulletin B-705-5A	Radiator valves for radiators.
Bulletin B-702D	Thermostatic traps for radiators.
Bulletin B-712B	Float & Thermostatic Traps for Heating coils and main drips, for spaces above second basement.
Bulletin B-709A	Strainers for Float & Thermostatic Traps.

COPY : COPIE

APPROVED

Except for space conditions clearances and dimensions subject to contract plans and specifications for this work.
SYSKA & HENNESSY

Date: Nov. 30, 1950 By W.W. (per M)

Recommended to Ch
4 June 1951.
Mr Zimmer wants to
talk to you on this
Stacy

-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

file

December 11, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Drive
ESTIMATE FOR CHANGE NO. 113 - TEMPORARY HEAT

Dear Mr. Dawson:

We are submitting herein our estimate for providing temporary heat for the Meeting Halls during the heating season of 1950 - 1951 for 121 consecutive calendar days starting on or about December 15, 1950.

HEATING INSTALLATION

The heating installation is to be made in accordance with the following Kerby Saunders, Inc. drawings:

Refrigeration Room -	Dwg.	KS-TH-11, dated 9/11/50
3rd Basement, North-	"	KS-50-41-101, dated 8/28/50
3rd Basement, South-	"	KS-50-41-102, " 9/15/50
2nd Basement, North-	"	KS-50-41-103, Rev. #1, dated 8/15/50
2nd Basement, South-	"	KS-50-41-104, dated 8/28/50
1st Basement, North-	"	KS-TH-09, dated 9/15/50
1st Basement, South-	"	KS-TH-10, " 9/11/50
1st Floor, North -	"	KS-TH-07, " "
1st Floor, South -	"	KS-TH-08, " "
2nd Floor, North -	"	KS-TH-05, " "
2nd Floor, South -	"	KS-TH-06, " "
3rd Floor, North -	"	KS-TH-03, " "
3rd Floor, South -	"	KS-TH-04, " "
4th Floor, North -	"	KS-TH-01, " "
4th Floor, South -	"	KS-TH-02, " "

CONDITIONS AND EXCEPTIONS RE HEATING INSTALLATION

The estimate for providing the heating installation, as per the above drawings, is based upon the following conditions and exceptions:

1. The permanent piping and unit heaters are to be used wherever possible.

Continued on Page 2 .....

2. All installation and removal work is to be done during regular working hours.

3. All salvageable material and equipment is to become the property of the United Nations. The cost of removing it and turning it over to the United Nations is included in Kerby Saunders, Inc. price. Space for its storage is to be provided by the United Nations.

4. The following materials and equipment are at present time stored by the United Nations. Kerby Saunders, Inc. has not figured on purchasing any new equipment or materials where those on hand will suffice:

   27 #345 Modine Unit Heaters and Switches
   74 #455 Modine Unit Heaters and Switches
   190' of 2½" Pipe
   8535' of 2" Pipe
   7355' of 1½" Pipe
   4170' of 1" Pipe
   1420' of 1¼" Pipe
   3500' of 3/4" Pipe
   62 Jenkins 1" #370 Gate Valves
   20 " 3/4" " " "
   6 " 1/2" " " "
   42 " 1/4" " " "
   95 K Master Traps, Strainer and Fittings ¼"
   90 " " " " " " ½"
   68 " " " " " " 3/4"
   20 Traps and Strainers 3/4"
   26 " " " 1/2"

   Please note the above unit heaters are in addition to those required by Change No. 62.

5. In locating temporary equipment, the Architectural plans are to be taken into consideration insofar as is possible so as not to interfere with building of walls, partitions, etc., or the work of other trades. The unit heaters, supply and return lines are to be kept sufficiently below the finished ceiling to permit the ceiling work to proceed.

6. The guarantee period for all permanent material and equipment is to start at inception of its use for temporary heat purposes.

7. The steam consumed for temporary heat is to be paid for by the United Nations.

8. A steam pressure of 30# is to be provided for operation of the temporary heating equipment.

Continued.....

9. From the time of temporary enclosure of the building, a temperature of at least 50° F shall be maintained during working hours, and not less than 40°F at all other times. From the time permanent windows, glazing and temporary doors are installed, a temperature of not less than 65°F shall be maintained for 24 hours a day and 7 days a week. At no time shall the interior walls and partitions, including the interior of exterior walls, be allowed to become chilled enought to allow condensation to collect on them.

10. When the building is enclosed by permanent windows and glazing and permanent or temporary doors, if the temperature of 65°F cannot be maintained with 30# steam for the proposed temporary heating system, Kerby Saunders, Inc. is to add sufficient units to maintain that temperature. These additions are to be made at no added cost to the U.N. or F-T-W-S, Inc.

TEMPORARY ELECTRICAL INSTALLATION

The temporary electrical distribution system is to be installed so that it will meet the requirements for power to operate the temporary heating system as shown on the Kerby Saunders, Inc. drawings listed hereinbefore.

CONDITIONS AND EXCEPTIONS RE TEMPORARY ELECTRICAL INSTALLATION

The estimate for providing and installing the temporary electrical work is based upon the following:

1. The Contract conduit, wiring, etc., for the permanent equipment in the 3rd and 2nd Basements is to be used insofar as general progress of the electrical work in the building will permit.

2. All installation and removal work is to be done during regular working hours.

3. All salvageable material and equipment is to become the property of the United Nations. The cost of removing it and turning it over to the United Nations is included in Fischbach & Moore's price. Space for its storage is to be provided by the United Nations.

4. Materials and equipment which were used for Temporary Heat in the Secretariat Building are to be used wherever possible. No new equipment and/or materials have been figured where such items on hand will suffice.

5. In locating temporary equipment, the Architectural plans are to be taken into consideration insofar as

Continued.....

5. (Continued from Page 3)

possible so as to not interfere with the building of walls, partitions, etc., orthe work of other trades. Wherever possible, wiring is to be kept below finish ceiling line in order to permit ceiling work to proceed.

6. Electric current is to be paid for by the United Nations.

7. Starters for Unit Heaters are to be installed by Fischbach & Moore, Inc., but furnished out of the stock of Unit Heaters previously used in the Secretariat Building. Starters for Trane Units are to be furnished by Kerby Saunders, Inc.

8. The electrical subcontractor is to guarantee that the electrical distribution system as set up by him will meet the requirements for power for the temporary heat installations.

MAINTENANCE LABOR

The estimates for maintenance labor are based upon using the minimum number of men allowable by present Union rules for three shifts per day (24 hours a day) and seven days per week.

An increase in the rate for electricians to $3.30 per hour is expected to take effect on January 1, 1951. All of Fischbach & Moore's maintenance costs in this estimate have been figured on the $3.30 per hour rate. At the termination of the 1950-1951 Temporary Heat season a proper credit will be issued to the United Nations for electrical maintenance labor at a lower rate prior to January 1, 1951 or for all maintenance labor at a lower rate if the contemplated wage increase does not take effect.

If, in actual operation, the requirements for maintenance men, as hereinafter set forth, are increased or decreased due to a change in Union requirements, a corresponding adjustment is to be made in the total amount of this estimate.

This estimate is based upon furnishing Temporary Heat at the various floor levels of the Meeting Halls Building after the permanent windows and doors have been installed and glazed. The estimate does not include the cost of enclosing any portions of the building with tarpaulins or other temporary enclosures since the extent of such work is indeterminate at this time. If such temporary closures are required, their cost will be covered by the estimate for another Change to be set up when the extent of such work can be determined.

 Continued.....

ESTIMATE FOR TEMPORARY HEAT

In accordance with the requirements and authority of Article 8(g) of our Contract HQ 1/75, we hereby offer you a reduction of Nine Thousand Three Hundred Dollars and Sixty Cents ($9,300.60) in our total maximum guaranteed cost price for the cost of furnishing and installing the above described Temporary Heating System and maintaining it for 121 consecutive calendar days (all as described herein), when compared with the Contract Allowance for Temporary Heat. This credit was determined as follows:

1. Temporary Heat Allowance established by Contract Documents $100,000.00

2. Installation Costs, including purchased materials, installation labor, dismantling labor, insurance, taxes, overhead and profit:

   (a) Kerby Saunders, Inc. $51,778.06
   (b) Fischbach & Moore, Inc. 6,428.00

   TOTAL $58,206.06

3. Maintenance Costs, including insurance, taxes, overhead and profit:

   (a) Kerby Saunders, Inc. $17,114.24
   (b) Fischbach & Moore, Inc. 15,379.10

   TOTAL $32,493.34

4. Summary

Contract Allowance		$100,000.00
Installation Costs	$58,206.06	
Maintenance Costs	32,493.34	90,699.40
NET CREDIT		$ 9,300.60

ATTACHMENTS

We are attaching hereto three copies of each of the following:

(1) Kerby Saunders, Inc. corrected quotation of September 14, 1950 to which is attached ...

(2) Kerby Saunders, Inc. supplementary quotation of October 20, 1950.

(3) Fischbach & Moore's "Pricing Sheet" - Estimate No. 9080", dated 10/3/50, covering installation costs.

Continued.....

ATTACHMENTS (Continued from Page 5)

(4) F-T-W-S, Inc. breakdown sheets, pages Nos. 1 and 2 inclusive, showing breakdown for all "Maintenance Labor" charges.

DEFINITION OF "121-DAY TEMPORARY HEATING PERIOD"

The above estimate is based on furnishing and maintaining temporary heat for the Meeting Halls Building during 121 consecutive calendar days starting on or about December 15, 1950.

The temporary heating period is to start on the day the United Nations approves our turning on the heat. The period is to end on the day on which the United Nations instructs us in writing to discontinue the use of temporary heat.

ADJUSTMENT FOR CHANGE IN LENGTH OF HEATING PERIOD

At the end of the heating period, the United Nations is to receive a credit of $270.00 per day for each calendar day that temporary heat has been supplied short of 121 days. If the heating period exceeds 121 days, Fuller-Turner-Walsh-Slattery, Inc. is to receive the additional sum of $270.00 per day for each calendar day in excess of 121. This figure of $270.00 per day is the average per day maintenance charge, based on the costs listed on the attached breakdown sheets.

CHANGE ORDER

On October 25, 1950 we received Mr. James A. Dawson's letter of 23 October 1950, authorizing us to proceed with the work for temporary heat, predicated upon a 121 day heating period. We have authorized Kerby Saunders, Inc. and Fischbach & Moore, Inc. to proceed with the work.

Will you please issue a Change Order - Deduction in the amount of $9,300.60. Will you also please authorize us to issue Change Order - Additions to Kerby Saunders, Inc. and Fischbach & Moore, Inc. in the amounts of $68,892.30 and $21,807.10, respectively, these Change Orders to be subject to adjustment as stipulated hereinbefore.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER*eab

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS JOB

CONTRACT HQ 1/75 December 11, 1950

ESTIMATE FOR CHANGE 113 - TEMPORARY HEAT
BREAKDOWN OF MAINTENANCE LABOR COSTS

I. 121-Day Temporary Heating Period

To start: On or about December 15, 1950.
To end: On or about April 14, 1951.

II. Steamfitters (Kerby Saunders, Inc.)

3 eight-hour shifts per day - 2 men per shift.

Cost per day

1 Steamfitter (1) 8 hour shift...	$18.64	
2 Steamfitters " " " " ...	37.28	
2 Steamfitters (3) 8 hour shifts @ $37.28	$111.84	$111.84
Welfare Fund 3% of Labor		3.36
		$115.20
Pension Fund 3% of Labor		3.36
		$118.56
15% Overhead & Profit		17.78
		$136.34
F.O.A.B. 4.56% of Labor		5.10
		$141.44

Total Cost per 24 hour day - $141.44

Total Cost 121 (24 hour) days @ $141.44 - $17,114.24

III. Electricians (Fischbach & Moore, Inc.)

Labor 200 hours per week	
200 at $3.30 per hour	$660.00
Insurance 12%	79.20
	$739.20
15% O. & P.	110.88
	$850.08
6% U.I. & F.O.A.B. on ($660.)	39.60
Per Week	$889.68
Per Day	$127.10

Continued.....

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS JOB

CONTRACT HQ 1/75 December 11, 1950

ESTIMATE FOR CHANGE 113 - TEMPORARY HEAT
BREAKDOWN OF MAINTENANCE LABOR COSTS
(Continued from Page 1)

IV. TOTAL MAINTENANCE COST PER DAY

Steamfitters	$141.44
Electricians	$127.10
	$268.54 (Say $270.00)

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 6, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Metal Toilet Enclosures

We are sending you herewith, for your information, one (1) print of the following Metal Toilet Enclosure Shop Drawings as approved for field distribution:

No.	Date	Title
611-Sheet 1 of 2	Rev. 11/22/50	Toilet Partitions 2nd & 3rd Basements
611-Sheet 2 of 2	" "	Toilet Partitions 1st Bsmt. to 4th Floor inclusive.

The following additional information has been added to the prints which we returned to the subcontractor marked "Approved 20 September 1950":

Item 1 - Notes on finish and color selection.
2 - Typical Elev. Layouts B & C
3 - Correction of ceiling Height "H" Mens Room 2B-57
4 - Correction of Typical front and side elevations to agree with correction Item No. 3

We have also added a note in red pencil on Sheet No. 1 of 2 that ceiling heights shown on Architect's drawing A-141, Rev. #15, are to be followed.

Since the added information is primarily for shop and field use, we are distributing the shop drawings, without resubmitting them for further approval.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 6, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Metal Toilet Enclosures

We are sending you herewith, for your information, one (1) print of the following Metal Toilet Enclosure Shop Drawings as approved for field distribution:

No.	Date	Title
611-Sheet 1 of 2	Rev. 11/22/50	Toilet Partitions 2nd & 3rd Basements
611-Sheet 2 of 2	" "	Toilet Partitions 1st Bsmt. to 4th Floor inclusive.

The following additional information has been added to the prints which we returned to the subcontractor marked "Approved 20 September 1950":

Item 1 - Notes on finish and color selection.
2 - Typical Elev. Layouts B & C
3 - Correction of ceiling Height "H" Mens Room 2B-57
4 - Correction of Typical front and side elevations to agree with correction Item No. 3

We have also added a note in red pencil on Sheet No. 1 of 2 that ceiling heights shown on Architect's drawing A-141, Rev. #15, are to be followed.

Since the added information is primarily for shop and field use, we are distributing the shop drawings, without resubmitting them for further approval.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL:eab

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 6, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Metal Toilet Enclosures

We are sending you herewith, for your information, one (1) print of the following Metal Toilet Enclosure Shop Drawings as approved for field distribution:

No.	Date	Title
611-Sheet 1 of 2	Rev. 11/22/50	Toilet Partitions 2nd & 3rd Basements
611-Sheet 2 of 2	" "	Toilet Partitions 1st Bsmt. to 4th Floor inclusive.

The following additional information has been added to the prints which we returned to the subcontractor marked "Approved 20 September 1950":

Item 1 - Notes on finish and color selection.
2 - Typical Elev. Layouts B & C
3 - Correction of ceiling Height "H" Mens Room 2B-57
4 - Correction of Typical front and side elevations to agree with correction Item No. 3

We have also added a note in red pencil on Sheet No. 1 of 2 that ceiling heights shown on Architect's drawing A-141, Rev. #15, are to be followed.

Since the added information is primarily for shop and field use, we are distributing the shop drawings, without resubmitting them for further approval.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcLweab

50-41 September 14, 1950

Fuller, Turner, Walsh, Slattery Inc.
403 East 42 St.
New York, N. Y.

Attn: Mr. C. W. Bartley

Re: Meeting Halls & Covering over East River Drive
Temporary Heat During Construction
Change No. 113

Gentlemen:

With reference to your letter of August 16, 1950 we have prepared layouts and estimates covering temporary heat equipment and piping installation and temporary heat maintenance costs.

The estimates are generally in accordance with the instructions of your letter and the layouts shown on the following drawings:

Refrigeration Room		MH-2
3rd Basement	North	MH-101
3rd "	South	MH-102
2nd "	North	MH-103
2nd "	South	MH-104
1st "	North	MH-H-17A
1st "	South	MH-H-17
1st Floor	North	MH-H-18A
1st "	South	MH-H-18
2nd "	North	MH-H-19A
2nd "	South	MH-H-19
3rd "	North	MH-H-21A
3rd "	South	MH-H-21
4th "	North	MH-H-22A
4th "	South	MH-H-22

The total cost for the temporary heating work installation is the sum of $51,184.79. + 593.27) - $51778.06 (See attached letter of 10/20/50)

The cost of the temporary heat maintenance for a total of ~~150~~ 121 days is the sum of ~~$21,216.00~~. 17114.24

Sheet #2
Fuller, Turner, Walsh, Blattery Inc.
September 14, 1950

The cost of temporary heat per 24 hour day is the sum of $141.44.

We suggest that a steam pressure of 30# be used for the temporary heating equipment operation.

We shall be glad to give you any additional information you may desire with this temporary heating project.

Very truly yours,

KERBY SAUNDERS, INC.

W. E. Hines

Enc.
WEH/cs

TEMPORARY HEAT FOR MEETING HALLS & COVERING

OVER EAST RIVER DRIVE

CHANGE NO. 113

Material

Pipe, Std. Steel -	3" - 80 ft. @ .57			$45.60
	* 2" 2450			--
	*1½" 3222			--
	*1¼" 1758			--
	* 1" 3110			--
	*3/4" 1786			--
Nips, Black Steel -	4"	1 @	.78	.78
	2"	50	.22	11.00
	1½"	50	.17	8.50
	1¼"	50	.14	7.00
	1"	450	.11	49.50
	3/4"	1050	.08	84.00
	1/2"	60	.07	4.20
Welding Tees -	5"	1 @	21.84	21.84
Welding Red. -	5"	1 @	9.94	9.94
Welding Flanges -	6"	2 @	7.88	15.76
	5"	6	7.00	42.00
	3"	8	4.38	35.04
Thread-O-Lets -	3"	1 @	3.46	3.46
	2"	15	1.73	25.95
	1½"	12	1.30	15.60
	1¼"	2	1.08	2.16
	3/4"	2	.86	1.72
Black C.I. Ells XH -	4"	1 @	4.72	4.72
	3"	14	3.60	50.40
	2"	79	1.05	82.95
	1½"	152	.75	114.00
	1¼"	84	.59	49.56
	1"	468	.41	191.88
	3/4"	405	.34	137.70
Black C.I. Tees XH -	3"	4 @	4.10	16.40
	2"	60	1.61	96.60
	1½"	82	1.18	96.76
	1¼"	46	.94	43.24
	1"	26	.70	18.20
	3/4"	125	.59	76.11
Black C.I. Ecc.Red. XH-	2"	1 @	2.50	2.50
	1½"	2	1.70	3.40
	1¼"	2	1.25	2.50
Black C.I. Unions XH -	2"	3 @	1.46	4.38
	1"	103	.69	71.07
	3/4"	248	.53	131.44

Stock

Black Caps -	4"	2 @	.96		$ 1.92
	3"	1	.62		.62
	2½"	1	.47		.47
	2"	14	.28		3.92
	1½"	11	.22		2.42
	1¼"	17	.16		2.72
	1"	22	.12		2.64
	3/4"	131	.10		13.10
Bolts & Gaskets (Sets)-	6"	1 @	1.40		1.40
	5"	5	1.31		6.55
	3"	8	.52		4.16
lves - Globe -	3"	2 @	25.63		51.26
	2"	14	15.00		210.00
	1½"	13	9.28		120.64
	1¼"	2	7.44		14.88
	1"	85	5.44		462.40
	* 1"	20			-- Stock
	* 3/4"	20			--
	3/4"	94	4.00		376.00
	1/4"	1	1.83		1.83
Hangers -	3"	7 @	.75		5.25
	2", 1½", 1¼" -		788 @	.50	394.00
	1" & under		480	.25	120.00
Press. Gage & Syphon -		1 @	7.80		7.80
trainers -	3/4"	125	2.25		281.25
Traps - Bucket -	* 1/2"	19			-- Stock
	* 3/4"	106			--
Press.Red. Valves & Strainers -	3"	1 @	165.00		165.00
Unit Heaters -	*	105			-- Stock
Welding Materials -					46.00
Pipe Joint Comp. Cutt'g. Oil -					100.00
MATERIALS					$3,974.09
2% City Sales Tax					79.48
					$4,053.57

(continued)

LABOR - 10,710 MH @ 3.10 $33,201.00 1,071 MH 3.35 3,587.85	$36,788.85
Welfare Fund 3% of Labor	1,103.67
Pension Fund 3% of Labor	1,103.67
	$43,049.76
15% Overhead & Profit	6,457.46
	$49,507.22
F.O.A.B. 4.56% of Labor	1,677.57
TOTAL	$51,184.79
	593.27
	$ 51778.06

* On hand by U.S.

TEMPORARY HEAT MAINTENANCE FOR

MEETING HALLS & COVERING OVER EAST RIVER DRIVE

1 Steamfitter (1) 8 hour shift	$18.64	
2 Steamfitters (1) 8 hour shift	$37.28	
2 Steamfitters (3) 8 hour shifts @ $37.28	$111.84	$111.84
Welfare Fund 3% of Labor		3.36
		115.20
Pension Fund 3% of Labor		3.36
		118.56
15% Overhead & Profit		17.78
		136.34
F.O.A.B. 4.56% of Labor		5.10
		$141.44

Total Cost per 24 hour day - $141.44

Total Cost ~~150~~ 121 (24 hour) day @ 141.44 - ~~$21,216.00~~ 17114.24

October 20, 1950.

Fuller, Turner, Walsh & Slattery, Inc.
403 East 42nd Street
New York 17, New York.

Att: Mr. C. W. Bartley.

Re: United Nations - Meeting Halls.
Temporary Heat
F. T. W. S. Change No. 113.

Gentlemen:

We wish to supplement our Sept. 14th, 1950 letter with the following data:

In reviewing our original estimate, we find that no allowance was made to replace the high pressure traps with the permanent low pressure traps specified. There are 32 traps involved in this operation plus pipe and fittings. The additional sum for this work is $593.27. The breakdown of this cost is attached hereto.

This cost should become part of our temporary heat order.

Very truly yours

KERBY SAUNDERS, INC.

J. D. Dobak
Project Engineer.

JD/eh

October 20, 1950.

Additional charge for replacing high pressure traps with permanent low pressure traps:

Labor.

32 Traps at 4 M. Hr. each.		
128 M.Hr. at $3.10/hr	$ 396.80	
13 M.Hr. at $3.35/hr	43.55	
	$ 440.35	
Welfare Fund 3%	13.21	
Pension Fund 3%	13.21	
	$ 466.77	$ 466.77

Material.

64 - 3/4" W.I. Nipples @ .22¢	14.08	
32 - 3/4" Unions @ .53¢	16.96	
	31.04	
Sales Tax 2%	.62	
	$ 31.66	31.66
		$ 498.43
15% Overhead & Profit		74.76
		$ 573.19
F.O.A.B. 4.56% of labor		20.08
Total Charge.		$ 593.27

COPY

120-5-18-8-

OREGON 9-3950

Hoffman
Ready for an immediate reply
13 Dec 50

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 11, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, N. Y.

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Contract HQ 1/82 - General Assembly and North Parking Garage
Stainless Steel Doors for Toilet Compartments

Dear Mr. Dawson:

In our letter of November 17, 1950 we advised you of the difficulty the Scherbak Specialties Company is having in getting any mill to accept their order for the 18-8 stainless steel they require for toilet compartment doors in the General Assembly and Meeting Halls.

Mr. Scherbak has informed us that he believes he can place an order for No. 430 (14-18) stainless steel. He has asked us to obtain your approval for making this substitution at no change in cost.

Will you please advise us promptly whether this change in material is satisfactory to you.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER:ar

Sift. Hopper - Rumpelter Hennegan 12/13 [illegible]

120 - 5-18-80

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

RECEIVED
DEC 12 1950
United Nations Headquarters
JAMES A. DAWSON

December 11, 1950

Gen File

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Heating, Ventilating and Air Conditioning
Ductwork - Shop Drawings

Dear Sir:

We are submitting herewith six (6) copies each of the following National Sheet Metal Work, Inc. Drawings for Ductwork being divided under the Heating, Ventilating and Air Conditioning subcontract of Kerby Saunders, Inc.

Drawing No.	2-S-11,	Ductwork 2nd Floor South,	Cols. 10 to 15 & T to V.
" "	PJ-1,	Ductwork in Projection Booths, Elev. 41' North & South on Column Line T.	
" "	3-N-1,	Ductwork 3rd Floor North,	Cols. 20 to 23 & Q to R Prime.
" "	1-S-11,	Ductwork 1st Floor South,	Cols. 8A to 10 and V to Y.
" "	1-S-10,	Ductwork 1st Floor South,	Cols. 8A to 15 and S to V.

Please review the above drawing and return three (3) copies together with your approval and/or comments at your earliest convenience.

Very truly yours,

P-J-1 - Ret'd 16 Feb. 1951

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

CER:WWS:bc

12/11/50

ISSUANCE OF DRAWINGS

OFFICE COPY

9Jan.1951

Meeting Halls
Fuller-Turner-Walsh-Slattery, Inc.

Mr. Blumquist

403 E. 42nd St.

messenger

3 each of:

1-S-11	2Dec.1950	1st Fl. South 10-8A and V to Y
2-S-11	5Dec.1950	2nd Fl. South T to V, 15 to 10
3-N-1	30Nov1950	3rd Fl. North 20-23 Q to R
1-S-10	4Dec.1950	1st Fl. South Cols. 8A to 15

all dwgs. approved as noted 8Jan1951 resubmit JTA

Nat. Sheet Metal submitted by K. Saunders

RECEIVED
JAN 9 1951
FULLER-TURNER-WALSH-SLATTERY
INCORPORATED

Left to Jean Burgeller Hannegan 12/13

120 - 5-18-8

OREGON 9-3950

RECEIVED
DEC 12 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 11, 1950

Gen Files

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York, New York

Re: Contract HQ 1/75 - Meeting Halls and Cover Over East River Drive
Heating, Ventilating and Air Conditioning
Shop Drawings

Dear Sir:

We are submitting herewith six (6) copies of each of the following drawings for materials being furnished under the Heating, Ventilating and Air Conditioning subcontract of Kerby Saunders, Inc.

National Sheet Metal Works, Inc. Dwg. No. 2-N-2, Ductwork 2nd Floor North, Cols. 18 to 22 & S to T.
" " " " " " " 2-N-7, Ductwork 2nd Floor North, Cols. 15 to 18 & S to T.
Kerby Saunders, Inc. Drawing No. 50-41-120, Panel Heating Coils, 3rd Floor South.

National Sheet Metal Works, Drawing No. 2-N-7 is being resubmitted as it has been corrected to conform with changes shown on drawing MH-H107-2.

Please review the above and return three (3) copies together with your approval and/or comments at your earliest convenience.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

CER:WWS:bc

12/12

ISSUANCE OF DRAWINGS

OFFICE COPY

3 Jan. 1951

Meeting Halls

Fuller-Turner-Walsh-Slattery, Inc.

403 E. 42nd St.

Mr. Blumquist

messenger

3 each of:

50-41-120 6Dec.1950 Panel Heating Coils

2M-2 25Oct1950 2nd Fl. North Bet. Cols. S and T

2M-7

all approved as noted 3Jan1951 resubmit JTA

submitted by K.Saunders, Inc.

RECEIVED
JAN 3 1951
FULLER-TURNER-WALSH-SLATTERY
INCORPORATED

120-5.18-8

OREGON 9-3950

Hoffman
Healy
Dwyer
Reese

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 11, 1950

Answer has our copy & will advise JJH. 21 Dec. 1950.

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Carpentry & Millwork - Shelving

In answer to Mr. J. J. Healy's recent inquiry, we wish to advise you that the Murray Hill Woodworking Corporation included in the price, upon which their subcontract is based, the furnishing and installing of two hundred 3'-0" units of standard stock metal shelving for the following spaces:-

Storage	3B30	Storage -	312	Storage	350
"	2B36	"	315	"	401
"	243	"	335	"	403
"	1B57	"	331	"	406
"	218	Sound Lock	371	"	422

The change from wood to metal shelving was made in accordance with Item 2 of Section No. 23 of "U.N. Comments of 12 December 1949 on Contractors Addenda of November 23, 1949".

Will you please advise us how these units are to be allocated to the various spaces.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese

C. E. Reese
Project Engineer

CER*eab

12/12

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 11, 1950

RECEIVED
DEC 12 1950
United Nations Headquarters
Co-ordinator of Construction

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Metal Doors, Frames and Trim

We are sending you herewith four (4) copies of Atlantic Metal Products, Inc. shop drawing, Sheet 14, Schedule Sheet Doors 1067 to 1095, inclusive, for your approval and/or comments.

The frame for door opening No. 1093 has been revised to provide a 7'-0" frame opening height with a 5-3/4" panel above it.

The frame for door opening No. 1095 has been revised to provide a 7'-0" frame opening height with a 2'-0" high panel above it.

The above noted changes are explained in our letter to you dated November 16, 1950 to which we attached a copy of a letter to the Atlantic Metal Products, Inc., instructing them to proceed with the alteration of the two frames. The change in contract cost for their work will be covered by Change No. 161.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

RECEIVED
DEC 15 1950
United Nations Headquarters
W. K. Harrison-Director of Planning

FMcL*eab

Hopper

Henly 12/13 [illegible]

120-5-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 11, 1950

RECEIVED
DEC 12 1950
United Nations Headquarters
JAMES A. DAWSON
Co-ordinator of Construction

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

To. Gen. File

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Miscellaneous Iron

We are sending you herewith four (4) prints of the following Miscellaneous Iron shop drawing submitted by General Bronze Corporation and C. E. Halback & Company:

HMS 51-6, dated 12/8/50 - Steel Framing For Booths Trusteeship Council Chamber

Will you please return two (2) prints of the above drawing marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C. E. Reese
C. E. Reese
Project Engineer

FMcL:eab

RECEIVED
DEC 15 1950
United Nations Headquarters
W. K. Harrison-Director of Planning

12/14

Hopper
Wesley
12/13
[illegible]

120-3-18-8

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT

403 EAST 42ND STREET

NEW YORK 17, N. Y.

December 11, 1950

RECEIVED
DEC 11 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

To Gen. File

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.

We are sending you herewith four (4) prints of the following Telephone Booth shop drawing submitted by Sherron Metallic Corporation:

ASM-1566, Rev. #2, dated 12/7/50 - Model 18-S Type 1 Telephone

The Sherron Metallic Corporation have advised as follows:

"The corrections shown on Drawing ASM-1566 do not affect our subcontract price. We will await approval of this drawing and choice of color before proceeding further."

Will you please return two (2) prints of the above drawing marked with your approval or necessary corrections.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

RECEIVED
DEC 15 1950
United Nations Headquarters
W. K. Harrison - Director of Planning
12/12

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

file

December 8, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, N. Y.

RE: CONTRACT HQ 1/75 - MEETING HALLS AND COVER OVER EAST RIVER DRIVE
ESTIMATE FOR CHANGE NO. 28
"Changes in Exterior Stairs No. 1, 2 and 3"

References:
a) U. N. Drawing RA-4, dated 5 May 1950 - "Exterior Stairs No. 1 & 2".
b) U. N. Drawing RA-5, dated 5 May 1950 - "Exterior Stair No. 3".
c) F-T-W-S Letter (Grogan) to United Nations dated 26 May 1950.
d) U. N. Drawing SK-308, dated 19 Dec. 1949 - "Exterior Stairs No. 1, 2 and 3".

Dear Sir:

In accordance with the requirements and authority of Article 8(g) of our Contract HQ 1/75, we do not claim any increase in our total guaranteed maximum cost price for the changes in the work as outlined by the "references" above.

The changes in stair tread nosings which show on the above plans are taken care of in our Change Estimate No. 18.

Will you please acknowledge receipt and acceptance of this estimate.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER:amc

120-3-18-80

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 8, 1950

RECEIVED
DEC 11 1950
United Nations Headquarters
JAMES A. DAWSON
(Co-ordinator of Construction)

Files 12/13

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr. Ornamental Iron

We are sending you herewith one (1) print of the following Ornamental Iron shop drawing as approved for field distribution:

GBM-55, revised 11/21/50 - Detail of Steel and Aluminum Trim for Fixed Windows

(General Bronze Corporation & C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL*eab

12/12

-82

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 8, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Ornamental Iron

We are sending you herewith one (1) print of the following Ornamental Iron shop drawing as approved for field distribution:

GBM-55, revised 11/21/50 - Detail of Steel and Aluminum Trim for Fixed Windows

(General Bronze Corporation & C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcL:eab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 8, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Ornamental Iron

We are sending you herewith one (1) print of the following Ornamental Iron shop drawing as approved for field distribution:

GBM-55, revised 11/21/50 - Detail of Steel and Aluminum Trim for Fixed Windows

(General Bronze Corporation & C. E. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcLeab

-8-

COPY

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
NEW YORK

December 8, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Dear Mr. Dawson: Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Dr.
Ornamental Iron

We are sending you herewith one (1) print of the following Ornamental Iron shop drawing as approved for field distribution:

GBM-55, revised 11/21/50 - Detail of Steel and Aluminum Trim for Fixed Windows

(General Bronze Corporation & C. R. Halback & Co.)

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

C E Reese
C. E. Reese
Project Engineer

FMcLmeab

FILE

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 7, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Headquarters
405 East 42nd Street
New York 17, N. Y.

Re: Contract HQ 1/75 - Meeting Halls and Covering over East River Drive
CHANGE NO. 157 - Change in Saddles

Reference (a) Mr. James A. Dawson's letter 1 December 1950 to F-T-W-S, Inc.

Dear Mr. Dawson:

On December 5, 1950 we received your letter, Reference (a), which reads as follows:

> "This letter is a confirmation of verbal instructions given to your Mr. W. Cunningham this morning.
>
> Submit for our consideration the prices which will be the result of substituting cast iron saddles with an abrasive surface for the nickel bronze saddles with an abrasive surface as listed on General Bronze' drawing GBM-47 and as detailed on GBM-48.
>
> Since you have given us verbal affirmation that there will be an overall credit, proceed on this basis, making all of the saddles, including the additional saddles of cast iron with an abrasive surface as outlined above."

Under the authority and requirements of the contract, we hereby request that proper adjustment of the contract price and contract time be dealt with under the terms and conditions of the contract. This change will be analyzed with all interested subcontractors and detailed estimates will be submitted to you as quickly as possible. Definite extension of contract time for completion will be requested as soon as determination can be made of the effect of this change on the entire job progress.

Very truly yours,
FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Progan

M. J. Progan
Project Manager

MJG:JTB*eab

Pumpletin
22 Mar. 51

OREGON 9-3950

FULLER-TURNER-WALSH-SLATTERY, INC.

UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

file

December 7, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, New York

RE: UNITED NATIONS CONTRACT HQ 1/75 - MEETING HALLS & COVER OVER EAST RIVER DRIVE - ESTIMATE FOR CHANGE NO. 76, 76A and 76B - Heating Changes

References:
a) United Nations Drawing SK-MH-H-107-1, dated 6/27/50
b) " " " SK-MH-H8A-3, " 6/30/50
c) " " " SK-MH-H-23-1, " 7/6/50
d) " " " SK-MH-H8A-2, " 6/28/50
e) " " Letter (Dawson) to FTWS dated 8/31/50

Dear Sir:

In accordance with the requirements and authority of Article 8(g) of our Contract HQ 1/75, we claim an increase in our total guaranteed maximum cost price in the amount of THREE THOUSAND FIVE HUNDRED NINETY FOUR DOLLARS AND EIGHTY EIGHT CENTS ($3,594.88) for the changes in steam piping, insulation temperature control work, grilles, and sheet metal ductwork, itemized herein which are required by the above "References".

Attached are three copies of each of the following:

1) Kerby Saunders' Estimate Sheet dated Nov. 16, 1950 (Page 1).
2) Kerby Saunders' Summary Take-off Sheet with Breakdown Sheets 1 to 5 inclusive.
3) Powers Regulator Co.'s Supporting Estimate dated Nov. 13, 1950, (Page 1).
4) William W. Short Co.'s Supporting Estimate dated Nov. 13, 1950, (Pages 1 and 2).
5) Westinghouse Electric Corp.'s Supporting Estimate dated Oct. 10, 1950 (Page 1).
6) National Sheet Metal Works' Supporting Estimate (Pages 1 to 3 inclusive).

Will you kindly issue a Change Order-Addition in the amount of $3,594.88 covering the revisions in the work itemized above.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER:amc
attach.

Bauman

-8-

OREGON 9-3950

file

FULLER-TURNER-WALSH-SLATTERY, INC.
UNITED NATIONS CONTRACT
403 EAST 42ND STREET
NEW YORK 17, N. Y.

December 7, 1950

Mr. James A. Dawson
Co-Ordinator of Construction
United Nations Planning Office
405 East 42nd Street
New York 17, New York

RE: CONTRACT HQ 1/75 - MEETING HALLS & COVER OVER EAST RIVER DRIVE
ESTIMATE (REVISED) FOR CHANGE NO. 14
Changes in Heating and Ventilating and Air Conditioning Work

References:
a) Mr. James A. Dawson's letter of 6 April to FTWS, Inc., "Heating and Ventilating".
b) Letter dated 5 April 1950 from Syska & Hennessy to Mr. James A. Dawson re: omission of 5" low pressure return line on Dwg. MH-H-16A between Cols. 20 and 21 in Column Lines "O" and "Q".
c) Mr. James A. Dawson's letter of 21 April 1950 - "Heating, Ventilating and Air Conditioning" to FTWS, Inc.
d) Syska & Hennessy Memorandum of 4 April 1950 (Minutes of Meeting of April 4, 1950 in their office).
e) "Bulletin of Changes No. 3" - Meeting Halls - Heating", dated 4 April 1950.

Dear Sir:

On September 15, 1950 we sent you our Estimate in the amount of $1,017.87 Addition for Change No. 14. This estimate has been revised to correct certain errors and now reads as follows:

In accordance with the requirements and authority of Article 8(g) of our Contract HQ 1/75, we claim an increase in our total guaranteed maximum cost price in the amount of EIGHT HUNDRED SEVENTY FIVE DOLLARS AND NINETY NINE CENTS ($875.99) for changes in heating, ventilating and air conditioning work outlined below which were required by the above "References".

Attached are three copies of Kerby Saunders' Estimate Sheets, 1, 2 & 3 dated November 30, 1950 including an attached photostat of his take-off sheet. Copies of National Sheet Metal Works Quotation, Powers Regulator Co. Quotation and W. W. Short's Quotation were attached to our original estimate dated September 15, 1950.

Will you kindly issue a Change Order-Addition in the amount of $875.99 covering the changes in work itemized above.

Very truly yours,

FULLER-TURNER-WALSH-SLATTERY, INC.

M. J. Grogan

M. J. Grogan
Project Manager

MJG:CER:amc
attach.

Kerby Saunders, Inc.

November 30, 1950.

F.T.W.S. Change Order No. 14
Our EWO Quotation No. 3 Job 50-41

DEDUCTIONS.		Labor	Mat'l.	Subs	Total
Dwg. MH-H-16A					
21' - 3" W. I. Pipe	@ .95		19.95		
2 - 3" Weld Ells	@ 3.67		7.34		
1 - 3" Weld Tee	@ 8.87		8.87		
3 - 3" Hangers	@ 1.50		4.50		
Insulation				14.00	
1 - MH @ 3.00/hr		3.00			
6 - MH @ 2.75/hr		16.50			
Dwg. MH-H-16A					
12' - 3" W. I. Pipe	@ .95		11.40		
2 - 3" Weld Ells	@ 3.67		7.34		
1 - 3" Hanger	@ 1.50		1.50		
Insulation				10.00	
1 - MH @ 3.00/hr		3.00			
5 - MH @ 2.75/hr		13.75			

ORIGINAL

100' - 4" Blk steel pipe	@ 1.31 -	131.00
2 - 4" Weld Ells	@ 5.73 -	11.46
2 - 5" Weld Tees	@12.17 -	24.34
11 - 4" Hangers	@ 2.00 -	22.00
	Mat'l -	188.80
Insulation	Subs. -	79.00
4 - MH @3.00/hr 12.00		
37 - MH @2.75/hr 101.75		
	Labor -	113.75

REVISED

100' - 3" Blk steel pipe	@ .95 -	95.00
2 - 3" Weld Ells	@ 3.67 -	7.34
2 - 5" Weld Tees	@ 8.87 -	17.74
11 - 3" Hangers	@ 1.50 -	16.50
	Mat'l -	136.58
Insulation	Subs.	62.00
3 - MH @ 3.35/hr 10.05		
23 - MH @ 3.10/hr 71.30		
	Labor -	81.35

	Labor	Mat'l.	Subs	Total
	32.40	52.22	17.00	
	68.65	113.12	41.00	

RECEIVED
DEC 1 1950
FULLER-TURNER-WALSH SLATTERY
INCORPORATED

Sheet No 2

Kerby Saunders, Inc.

November 30, 1950.

F.T.W.S. Change Order No. 14
Our EWO Quotation No. 3

Job 50-41

DEDUCTIONS		Labor	Mat'l	Subs.	Total
Brought Fwd. Sheet 1		68.65	113.12	41.00	
Dwg. MH-H-16A					
82' - 1-1/2" Blk steel pipe	@ .18		14.76		
82' - 1-1/2" W. I. pipe	@ .38		31.16		
82' - 1" Brass pipe	@ .57		46.74		
4 - 1-1/2" C. I. Ells	@ .22		.88		
2 - 1" Brass Ells	@ .68		1.36		
17 - 1-1/2" Hangers	@ .75		12.75		
9 - 1" Hangers	@ .50		4.50		
Insulation				80.00	
3 - MH @ 3.00/hr		9.00			
27 MH @ 2.75/hr		74.25			
40 sq. ft. C. I. Radiator	@ .60		24.00		
Radiator Valve & Trap	@8.00		8.00		
Pipe & Fittings	@3.00		3.00		
2 - MH @ 3.00/hr		6.00			
12 MH @ 2.75/hr		33.00			
24' - 5" W. I. Pipe	@1.80		43.20		
5 - 5" Hangers	@2.00		10.00		
Insulation				18.00	
2 - MH @ 3.00/hr		6.00			
13 MH @ 2.75/hr		35.75			
Dwg. MH-H-16A					
15' - 1-1/2" W. I. Pipe	@ .38		5.70		
2 - 1-1/2" Ells	@ .22		.44		
1 - 1-1/2" Tee	@ .34		.34		
3 - 1-1/2" Hangers	@ .75		2.25		
Insulation				9.00	
1 - MH @ 3.00/hr		3.00			
3 - MH @ 2.75/hr		8.25			
		243.90	322.20	148.00	
Sales Tax 2%			6.44		
Welfare Fund 3%		7.32			
		251.22	328.64	148.00	
Total Net Deduction for Temp. Control (Powers Regulator Co)		251.22	328.64	140.00 288.00	867.86
F.O.A.B. 4.56% of labor					11.12
Grand Total of Deductions					$878.98

COPY

RECEIVED
DEC 1 1950
FULLER-TURNER-WALSH SLATTERY
INCORPORATED